








- WELCOME AND INTRODUCTIONS
- TASK FORCE VIRGIN ISLANDS PUERTO RICO
- PROJECT OVERVIEW & VISION
- EXISTING CONDITIONS & IMPACTS
- RIO PUERTO NUEVO INDIVIDUAL CONTRACTS
- MOVING FORWARD WITH CHANGE



USACE TASK FORCE VIPR



Provides additional leadership bandwidth and focus on priority missions in USVI and PR





TF VIPR ENGAGEMENT IN PUERTO RICO



Program Value in Excess of >\$6B

Civil Works and Public Infrastructure (Approved Funding Levels*)

Rio Puerto Nuevo	\$1.585B			
Rio de la Plata	\$485M			
Rio Grande de Arecibo	\$174M	Guajatac	a Dam Brook	
Caño Martin Peña	\$163.3M	Guajatas	a Dam Rio Grande d	Rio de la Plata / Carrodan Harbon
Rio Culebrinas	\$40M	Rio Culebrinas		PR Coastal Study – Ocean Park
Rio Grande de Manati (Ciales)	\$14.8M	M		Fort Buchanan Puerto Nuevo ARC
Rio Guayanilla	\$60.6/220M			Fort Buchanan \ Puerto Nuevo ARC Rio Puerto Nuevo
Rio Guanajibo	\$107M	PR Coastal Study – Rincón		Rio Grande de Manati at Ciales
Rio Nigua at Salina	\$47.8M	Tit Goastal Glady Tilloon		Rio Aibonito
San Juan Harbor	\$45.6M	Rio Guanajibo at Mayagüez		
Guajataca Dam	\$1B			
PR Coastal Study	\$6.3M			Camp Santiago JTC
			/ Rio Guayanilla	Rio Nigua at Salinas
	41 🔿 4 41	•	i vio Quayanilla	

Military and Work for Others (Active Construction)

PR National Guard Camp Santiago Joint Training Center	\$291M
FDA San Juan Facility	\$10M
Fort Buchanan Army Family Housing	\$31.9M
Fort Buchanan Antilles Middle School Replace HVAC	\$3.49M
Fort Buchanan Physical Fitness Facility	\$10.08M
Fort Buchanan Army Reserve Center Training Bldg	\$19.27M
Puerto Nuevo Army Reserve Center Energy Resilience	\$9.6M

Civil Works and Public Infrastructure



Military and Work for Others

*NOTE: Current cost estimates exceed approved funding levels on many projects.





RIO PIEDRAS – EXISTING CONDITIONS



RIO PUERTO NUEVO OVERVIEW













COMPLETED (COST SHARED)

CONTRACTS 1, 1A, 2A/AR, 2AA, 2C1, 2D WALLS

STATUS: 2D Walls, last completed, was May 2022. AMOUNT: \$470M

- Kennedy Bridge seismic retrofit; 36-inch water line
- First 1.3 miles of channel improvements
- Quebrada Margarita channel excavation and confluence walt lower Puerto Nuevo channel dredging
- Bechara Channel secant pile wall box culvert: 90-inch sewer line modification; open channel work
- De Diego Expressway Bridge abutments; east and west pier drill shaft reinforcement
- Quebrada Margarita Stilling Basin
- Construction of 350-foot left channel wall and 750-foot right channel wall at channel confluence.

ONGOING (SUPPLEMENTAL) CONSTRUCTION

CONTRACT - LA CHULETA

 Upland Material Management Area (future) capacity of ~350,000 cubic yards of material)

REMAINING (SUPPLEMENTAL) CONSTRUCTION

CONTRACT 1 | UPPER MARGARITA CHANNEL

- Sewer line relocation
- Construction of .63 miles of channel improvements at Upper Quebrada Margarita

CONTRACT 2 | ROOSEVELT BRIDGE

- Roosevelt Avenue Bridge replacement
- CONTRACT 3 | MAIN CHANNEL (RIO PIEDRAS)
- Channel walls
 1.1 miles of Main Channel improvements

CONTRACT 4 | LAS AMERICAS BRIDGES

- · Channel, Stilling Basin and Bridge Replacements
- ▶ 4A-1: Las Americas Expressway Bridge 4A-2: Piñero Avenue Bridge East
- ▶ 4A-3: Northeast Access Ramp Bridge
- ▶ 4A-4: Southeast Access Ramp Bridge

CONTRACT 5 | NOTRE DAME & W. PIÑERO BRIDGE

- 5A: Notre Dame Bridge replacement
- 58: Piñero Avenue Bridge West replacement; Quebrada Josefina downstream to Río Piedras

CONTRACT 6 | MAIN CHANNEL / BUENA VISTA


- 1.75 miles of Rio Piedras channel improvements
- 4 bridges (2 new; 2 replacements)
- .80 miles channel diversion at Quebrada Buena Vista

CONTRACT 7 | JOSEFINA & DOÑA ANA CHANNEL

- 10 bridge replacements
- 5000 LF, of Quebrada Josefina and 4400 LF, of Quebrada Doña channel improvement

CONTRACT - BECHARA

 Upland Material Management Area (future) capacity of ~600,000 cubic yards of material)



Sponsor: PR Department of Natural and Environmental Resources (DNER)

Funding: Approved Current Working Estimate \$1,584,982,000 (funds available at HQUSACE). Current Cost Estimate (NOV 2022 Cost Estimate) \$3,595,668,000 (100% Federal)

Description and Status:

- o Construction will be accomplished in 17 contracts. Six contracts have been completed and ten contracts are currently in design. Upcoming contracts to be awarded are Contract 2 in March 2024 and Contract 3 in Winter 2024. The project's construction completion is expected in 2033.
- This project was fully funded by the Bipartisan Budget Act of 2018 (BBA 2018), however current cost estimates exceed approved funding levels.

Updates:


- o Team continues working with communities along Rio Piedras and Reparto Metropolitano. There has been significant progress made, with more to come.
- There is a heavy emphasis of Engineering with Nature on the design, collaboration with ERDC and continuing input from communities. Reduction of >30 acres of concrete from the project!


Construction Temporary Impacts:


- Minor temporary impacts to environment during construction
- Removal of trees to allow construction access
- Maintenance of traffic
- Temporary inconvenience

RIO PUERTO NUEVO – PRE PROJECT CONDITIONS

- 26 square miles of highly urbanized, densely populated flood basin
- Existing channel overflows above 2year storm event (bank full)
- Bank full refers to the water level stage that just begins to spill out of the channel into the floodplain.
- Bank full flows tend to occur frequently, on the average every two years (50% chance each year), its how the river form its channel; natural river process.







RPN CNT-6A/6B RIO PIEDRAS/MAIN CHANNEL DATED: 1963













- Rio Piedras was channelized in the 1950's-1960's
- Original meandering river was changed to a man-made channel once San Juan was developed and urbanized





Legend:

Channelized River

1,1

Original Natural River


RIO PUERTO NUEVO – IMPORTANCE OF PROJECT





Note: Video taken on corner of Calle Interamericana and Calle Oxford showing flooding of Rio Piedras during a 5 to 10-yr storm event from Hurricane Lenny on November 15-19, 2009.

Credit: https://www.youtube.com/watch?v=T osfiDlaqA



Note: Profile above highlights Notre Dame Bridge flooding between recently seen 1-2 yr events (~10-ft water elevation) and a 100-year storm event which would increase flooding by an additional ~8-ft.



RIO PIEDRAS:




EXPECTED 100 YEAR FLOODING (1% CHANCE OF ANNUAL EXCEEDANCE)







RIO PIEDRAS – HISTORICAL EROSION









RIO PIEDRAS – HISTORICAL EROSION













RIO PIEDRAS – HISTORICAL EROSION





- Erosion of the banks continue at an accelerated rate
- Doing nothing risks more trees falling in to river on their own and higher risk of obstruction downstream




MUNICIPAL DRAINAGE VS RIVER FLOODING




Stormwater Ground surface Storm Ground surface Storm Ground surface Storm Catch basin Stormwater Large Head Difference: Water will drain quickly from the surface Receiving waterbody

Outfall pipe



Credit: https://www.charleston-sc.gov/1999/High-Tides-Affect-Drainage-Systems



Credit: https://onlinelibrary.wiley.com/doi/full/10.1111/jfr3.12617

- Replacement of drainage system along will not resolve the localized flooding. Drainage systems require an outlet.
- Proper capacity of rivers, tributaries are required for successful discharge of pluvial accumulation





RIO PUERTO NUEVO – INDIVIDUAL CONTRACTS

RPN CNT-1 UPPER MARGARITA CHANNEL










- Upper Margarita Channel (Sta. 56+00 to Sta. 89+60)
- Construction of concrete channel to tie to existing stilling basin
- Magnitude of Construction: \$100M to \$250M
- Period of Performance: 4.5 years












RPN CNT-2 ROOSEVELT AVE. BRIDGE

- Roosevelt Avenue Bridge with a temporary detour bridge construction
- Six-lane, pre-cast pre-stressed concrete beam bridge
- Magnitude of Construction: \$25M to \$100M
- Period of Performance: 4 years
- 110 Ea. six-foot diameter concrete-drilled shaft piles (~90 feet deep)
- 90 Ea. five-foot diameter concrete-drilled shaft piles (~90 feet deep)
- 19,000 cy of concrete
- 7,000 tons of reinforcing steel
- 119,000 cy of excavated material for disposal




















RPN CNT-3

MAIN CHANNEL (RIO PIEDRAS)






















- Main Channel Walls, composite steel pipe pile/steel sheet pile walls
- Magnitude of Construction-\$250M to \$500M
- Period of Performance 5 years
- **Estimated Advertisement: Early** 2024
- 1,600 6' Dia. Concrete Drill Shaft Piles (~80' deep)
- 142,000 CY of Concrete
- 32,000 TN of Reinforcing Steel
- 637,000 CY of excavated material to be disposed
- 83,000 CY of suitable fill



129+00,0000



RPN CNT-4: LAS AMERICAS BRIDGES
















- Bridge replacement of four major existing bridges over the Piñero Avenue Interchange
 - 4A-1) Las Americas Expressway Bridge
 - 4A-2) Piñero Avenue Bridge East
 - 4A-3) NE Access Ramp Bridge
 - 4A-4) SE Access Ramp Bridge
- Concrete channel construction
- Magnitude of Construction: \$250M to \$500M
- Period of Performance: 5 years
- Significant Maintenance of traffic
- Six-foot diameter concrete drill shaft for bridge abutments and channel walls
- Channel bottom will be articulated concrete block mattresses (ACBM)
- Channel: 1,200 Ea. five-foot diameter concrete drilled shaft piles (~90 feet deep)











RIO PUERTO NUEVO – DESIGN UPDATES CHANGES TO CONTRACT 4











RPN CNT-5A: NOTRE DAME BRIDGE













- · Channel works underneath bridge
- Temporary one-lane bridge
- Permanent pedestrian bridge
- Maintenance of traffic through Calle Notre Dame
- Magnitude of Construction: \$25M \$100M
- Period of Performance: 3 years
- Six-foot diameter concrete drill shaft for bridge abutments and channel walls
- Channel bottom will be ACBM
- 100 Ea. 6-foot dia. concrete drilled shaft piles (~106 feet deep)











RPN CNT-5B: W. PIÑERO AVE. BRIDGE

- Piñero Avenue Bridge West replacement
- Channel works underneath bridge and downstream
- Maintenance of traffic on Piñero Avenue
- Magnitude of Construction: \$100M \$250M
- Period of Performance: 5 years
- 200 Ea. five-foot diameter concrete drilled shaft piles (~90 feet deep)
- 52,000 cy of concrete
- 2,250 tons of reinforcing steel
- 76,000 cy of excavated material to be disposed
- 1,400 LCY of suitable fill
- 14,000 tons of steel sheet pile
- 102,000 square feet of ACBM
























RPN CNT-6A/6B RIO PIEDRAS/MAIN CHANNEL











< 1-year storm event



13 Oct 2021 Notre Dame Bridge during flood waters from Rio Piedras. This is less than a 1-year (100% chance of occurring in a given year) storm event.

5-10-year storm event



Note: Video taken on property immediately south of Notre Dame Bridge showing flooding of Rio Piedras during a 5 to 10-yr storm event from Hurricane Lenny on November 15-19, 2009.









- Team has recommenced work on CNT-6A as it is not affected by ecological corridor law.
- CNT-6B is critical and has approximately 11-13% of the overall project benefits in this area. Significant protection to Villa Nevares community.
- Areas that will be constructed in UPR land will have MINIMAL environmental impact and is being design to work WITH NATURE.
- Trees are currently falling in to Rio Piedras due to erosion and expected to continue.

RPN CNT-6A/6B RIO PIEDRAS/MAIN CHANNEL

















OLD DESIGN 1991






















Figure 1. Project are south of Americo Miranda

Challenges: To successfully design our project, the channel must be constructed in the dry alongside the existing channel. This unfortunately necessitates the properties on one side of channel.



Figure 2: Rendering showing what new channel and new linear green belt/park will look like once construction completed in this area.



Figure 3: Example of actual construction similar to what the Josefina and Doña Ana Channels will look like upon completion.

RPN CNT-7 CURRENT CHANNEL CONDITIONS











Figure 1: Image of existing conditions in Quebrada Josefina.



Figure 2: Image of existing conditions of Andalucia bridge.



Figure 3: Image of impacts in Quebrada Josefina as a result of 27 October 2023 rain event.





Figure 4 and 5: Images of existing condition and repairs performed by MSJ due to impacts from 27 October 2023 rain event.



BECHARA MATERIAL MANAGEMENT AREA & LUIS MUÑOZ MARIN PARK POND









Bechara Material Management Area



LMMP – Material Placement and Staging

- NEPA ongoing with Public Meeting upcoming
- Design nearing completion on Park
- Bechara Design award next month






MOVING FORWARD WITH CHANGE


RIO PUERTO NUEVO – NEPA TIMELINE





RIO PUERTO NUEVO – RECREATIONAL FEATURES





LINEAR PARK/BICYCLE PATH:

- Plans for a linear park and bike path that connects all communities adjacent to the project to the Luis Muñoz Marin Park.
 - Includes a path from Puerto Nuevo
 Norte (thru Roosevelt Avenue Bridge)
 - Includes linear park and paths from Reparto Metropolitano thru Piñero Avenue pedestrian crossing.
 - Includes a path from University of Puerto Rico through the Villa Nevares

 Jardines Metropolitano / University
 Gardens areas, crossing over at Notre
 Dame Bridge
- Replanting of vegetation and trees equal in number to the ones removed (native, noninvasive species)
- One Service Bridge connecting both sides of park at the southern end of Luis Munoz Marin Park





COMMUNITY ENGAGEMENT SUCCESSES / CHALLENGES



SUCCESSES:

- TRUST CONTINUING TO BE BUILT WITH COMMUNITIES!!!
- Team has spent the last 5 years continuously meeting with communities. (estimated 20-30 separate meetings)
- Input and Feedback from these meetings have been realized and directly improved design. "Results have been demonstrated"
- Collaboration with ERDC with strong emphasis on Engineering With Nature (EWN). "Director of ERDC visited project & pleased with progress"
- Significant reduction in concrete throughout Rio Piedras, eliminating majority of concrete channel bottom (30 acres) and additional reduction of 17 acres of concrete. "Greener Project"





CHALLENGES:

- Continue work with communities, local and state government in getting all the factual information regarding the project benefits
- Getting communities to recognize that their input and feedback is being incorporated with Nature Based solutions.
- Mutual Understanding of Engineering with Nature/Nature Based Designs.
- Continue providing scientific design information that is understand by all stakeholders. (technical & non-technical)







RIO PUERTO NUEVO:

REALIZED BENEFITS FROM COMPLETED PROJECT











PARTNERSHIP WITH MUNICIPIO DE SAN JUAN





WHERE ARE WE NOW? / WHERE WILL WE BE?



PURPOSE: The primary purpose of the authorized project is to improve human health and safety, and to provide additional incidental economic benefits (recreation, redevelopment, etc.) through flood risk management and reduction in damages to structures, contents, and transportation infrastructure within the Río Puerto Nuevo Basin.

EXISTING IMPACTS:

- · Continued risk to health and safety of communities:
- Impacts to environment, economy, infrastructure and personal property
- · Trees along the bank will continue to fall in and block river flow

CONSTRUCTION TEMPORARY IMPACTS:

- Minor temporary impacts to environment during construction
- · Removal of Trees to allow construction access
- Maintenance of Traffic
- Temporary Inconvenience

BENEFITS:

- Significant reduction of flood risk to San Juan and communities adjacent to project
- Improved Infrastructure (new utilities, replaced sanitary sewer and electrical)
- Robust new bridges and roadways that are alongside project
- New Linear Parks and recreational areas adjacent to the project
- New landscaping and Native trees along project













CHALLENGES





Constructability (Means and Methods):

- Limited Space: Constructing flood walls under existing bridges with low overhead clearances, limited construction staging and access
- Water Diversion and Care: Working within the channel footprint along the rivers while maintaining existing flow
- Material Disposal and Hauling: Cut from the channel and disposal
- Traffic Control: Maintenance of traffic during construction in highly urban area.

Real Estate:

- Availability of housing for home relocation
- Public Perception over process

General:

- Coordination and close partnering with key Commonwealth Agencies
- Public push for minimal environmental impacts and nature based designs



QUESTIONS?



